

MYSORE DIVISION.

Notice dated 25th September 1928.

Notice is hereby give that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M., on 20th October 1928, for restoring the breached Bommanhalli Minor Tank, Registered No. 27 of Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit Rs. 250 two hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the breached Bommanahalli Minor Tank, Registered No. 27 of Nagamangala Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

Abstract estimate for restoring Bommanahalli minor tank, Registered No. 27 at Nagamangala Taluk.

No.	Items of work	Per	Rate	Quantity
	<i>Bund.</i>		Rs. a. p.	
1	Clearing jungle on bund	Lumpsum		...
2	Earthwork to bund with watering and tamping, etc., complete.	...		19,308
3	Removing and resetting the existing old rough stone work with new jelly.	Cyd.		700
4	Rough stone work new with jelly backing	"		2,109
5	Gravelling to slopes, top and backing revetment	"		2,417
6	Providing grade stones including cutting figures and painting.	Each		37
7	Providing index stones	"		37
8	Do gauge stone	"		1
9	Do register number stone	"		1
10	Do date stone	"		1
11	Do B. M. stones	"		2
	<i>Breach filling.</i>			
12	Clearing sand, silt, etc., in the breach	Cyd.		1,111
13	Cutting steps and grips at either ends of breach	Lumpsum		...
14	Earthwork filling breach with a mixture of 1/3 of good gravel and 2/3 clay with watering and tamping.	Cyd.		1,535
15	Puddle wall with clay	"		767
16	Gravel backing to revetment, slopes and top of bund	"		229
17	Rough stone revetment with jelly backing	"		492

No.	Items of work	Per	Rate	Quantity
<i>Sluice No. 1.</i>			Rs. a. p.	
18	Earthwork cutting and opening bund and excavating foundations.	Cyd.		279
19	Surki concrete	C.ft.		475
20	Burnt brick in surki mortar	"		777
21	Burnt stone slabs 6" thick dressed and fixed in mortar	S.ft.		259
22	Surki plastering	Sqr.		8'25
23	Providing plug and rod with locking arrangements	Lump sum		...
24	Cutting orifices	Each		4
25	Earthwork refilling bund with watering and tamping, etc., complete.	Cyd.		279
<i>Sluice No. 2.</i>				
26	Earthwork cutting open and excavating foundations ..	Cyd.		177
27	Filling bund with watering and tamping	"		177
28	Surki concrete	Cft.		475
29	Burnt brick in surki mortar	"		777
30	Burnt stone slabs 6" thick dressed and set in mortar...	Sft.		259
31	Surki plastering	Sqr.		8'25
32	Providing plug and rod with locking arrangements ...	Lump sum		...
33	Boring holes for orifices and guide slabs	Each		4
<i>Left Weir.</i>				
34	Earthwork excavation, soil being sheet rock mixed with soft rock.	Cyd.		111
35	Benching rock for making seat of masonry walls even.	Sft.		1,331
36	Surki concrete	Cft.		1,075
37	Burnt brick in surki mortar	"		3,464
38	Burnt stone slabs 6" thick nicely dressed	Sft.		331
39	Do 4" do	"		418
40	Surki plastering	Sqr.		34'79
41	Joggle joints to coping slabs of weir	Each		28
42	Draft clearing at the weir	Lump sum		...
43	Jelly filling for the extra depth at apron	Cyd.		330
44	Rough stone work new with jelly packing	"		497
<i>Pipe Aqueduct.</i>				
45	Earthwork excavation and filling	"		49
46	Surki concrete	Cft.		125
47	Burnt brick in surki mortar	"		1,028
48	Burnt stone slabs 6" thick nicely dressed	Sft.		24
49	Boring holes in slabs for holding down bolts	Each		12
50	Constructing coping over parapet 6" thick with brick in mortar and surki plastering, complete.	R.ft.		92
51	Surki plastering	Sqr.		9'08
52	Iron clamps 2" wide and 1" thick plate with holding down bolts 2½ feet long and 1½ inches diameter with nuts, washers, etc., complete.	Each		3
53	Rough stone work new with jelly packing	Cyds.		11
54	Cast iron pipes 12" diameter to the site including fixing charges, etc.	R.ft.		65
55	Extra earthwork for drains, turfing and other unclassified charges.	Lump sum		...
56	Blocking up the existing dilapidated sluice in C.S. 7...	Lump sum		...